

## HIGHWAY 427 SB

The project consisted of both intermittent and continuous repair on several areas of the 427 SB press route mainline. Normal-weight precast concrete Super-Slab panels were used for full-depth replacement. Traffic was detoured onto the parallel collector road to allow access to all 3 of the press lanes during the night-time closure.

### Slab Details

Slab Dimensions: 3.66M Wide (Avg.) X 3.5M Long (Avg.) X 215mm thick  
Slab Area: 15,150 SF (1,408 SM)  
No. Slabs: 115  
Surface Type: All slabs were single plane

### Slab Installation

Installation Dates: October, 2008  
Months of Installation: 1  
Production Rate: 10 slabs/night (average)

### OWNER

The Ministry of Transportation

### CONSULTANT

URS

### CONTRACTOR

Brennan Paving

### LOCATION

Toronto, Ontario

